

Visionera Pvt Ltd

Sujathanagar, Pendurthi, Visakhapatnam, Andhra Pradesh, 531173
GSTIN: 37AAJCV0447L1ZX

Ph: 9347475257

E-mail: bdo2.zy@myntreal.com

Ref: MNR-SLR0001-0097

Date: 11-07-2026

To,

Ganesula Anasurya

Vellangi East Godavari

East Godavari, Andhra Pradesh

Estimation for Supply of 3KW Solar Power Generating System (SPGS) - On-grid for Net meter

Solar Panel: 3000W

APS

DCR Solar Panel

Solar Inverter: 3kVa Grid Tie Solar Inverter (IEC/BIS Approved)

Accessories: 4Sq. Copper AC Cable,

4Sq. Copper DC cable

GI Mounting Structure

(North Pole—6 Feet, South Pole—4 Feet)

AC-DCDB, Earthing,

1" PVC Pipe, Flexible PVC Pipe

GI/SS Nuts, Bolts & Hardware

Price (Including GST)

Rs.250,000.00

Discount

Rs.10,000.00

Final Amount

Rs.240,000.00

Application Charge

Actuals

Net Meters Cost

Actuals (Estimating given by APEPDCL)

MNRE SRT National Solar Portal Subsidy

Rs.78,000.00

The above prices are for the complete SPV kit which includes SPV modules, Solar Inverter, Structure & all Accessories. Fabricated Shed, High Rise Structure, Civil Work, Net Meter Equipment, Extra cables (AC-DC), Contract Load Enhancement Charges, Special Drawings & Internal Wiring are customer scope.

Above system designed for S.No. —

Discom Sanction Load: 3-Cat-1-Phase-1

Terms and Conditions:

1. Taxes: GST Included 2. Payment terms: 100% Advance upon placing order. 3. Delivery: 2-4 weeks

Our Banking Details (CC Account)

A/c Name: Visionera Pvt Ltd

A/c No.: 50200078831450

Bank: HDFC, NAD Kotharoad

NEFT/RTGS/IFSC: HDFC0001604

Product Warranty

Modules: As per MNRE guidelines IEC/BIS standards

1. 10-year workmanship warranty (Minimum power output 90% for first 10 years; 80% from Year 11 to 25)

2. 25 Years Life

Solar Inverter: As per IEC/BIS Standard

1. 5 year warranty against manufacturing defects

Authorised Signatory

T. Jyothirmai

Stamp



Authorised Partners

