xyzc
Visakhapatnam, Andhra Pradesh - 530001, Visakhapatnam, Andhra Pradesh, 530001
GSTIN: chrohsfwa682

Ph: 1122334455
E-mail: xyzc@gmail.com
✔ MNRE Empanelled Vendor

Ref: xyz-00-001 **Date: 06-10-2026**

To,
raghu
gajuwaka, visakhapatnam
visakhapatnam

Estimation for Supply of 3KW Solar Power Generating System (SPGS) - On-grid for Net meter

Solar Panel: 3000W
Tata
DCR Solar Panel

Solar Inverter: 3kVa Grid Tie Solar Inverter (IEC/BIS Approved)

Accessories: 4Sq. Copper AC Cable,
4Sq. Copper DC cable
GI Mounting Structure
(North Pole–5 Feet, South Pole–3 Feet)
AC-DCDB, Earthing,
1" PVC Pipe, Flexible PVC Pipe
GI/SS Nuts, Bolts & Hardware

Price (Including GST)	Rs.210,000.00
Discount	Rs.10,000.00
Final Amount	Rs.200,000.00
Application Charge	Actuals
Net Meters Cost	Actuals (Estimating given by APEPDCL)
MNRE SRT National Solar Portal Subsidy	Rs.78,000.00

The above prices are for the complete SPV kit which includes SPV modules, Solar Inverter, Structure & all Accessories. Fabricated Shed, High Rise Structure, Civil Work, Net Meter Equipment, Extra cables (AC-DC), Contract Load Enhancement Charges, Special Drawings & Internal Wiring are customer scope.

Above system designed for S.No. —
Discom Sanction Load: 3-Cat-1-Phase-1

Terms and Conditions:
1. Taxes: GST Included 2. Payment terms: 100% Advance upon placing order. 3. Delivery: 2-4 weeks

Our Banking Details (CC Account)
A/c Name: xyzc
A/c No.: —
Bank: —
NEFT/RTGS/IFSC: —

Product Warranty

Modules: As per MNRE guidelines IEC/BIS standards
1. 10-year workmanship warranty (Minimum power output 90% for first 10 years; 80% from Year 11 to 25)
2. 25 Years Life
Solar Inverter: As per IEC/BIS Standard
1. 5 year warranty against manufacturing defects

MNRE NATIONAL SOLAR PORTAL (PMSURYAGHAR) EMPANELLED VENDOR

Authorised Signatory **Stamp**