

Visionera Pvt Ltd

Sujathanagar, Pendurthi, Visakhapatnam, Andhra Pradesh

GSTIN: 37AAJCV0447L1ZX

Ph: 9347475257

E-mail: bdo2.zy@myntreal.com

Ref: MNR-SLR0001-0001

Date: 08-04-2026

To,

NAKKA VENKATA LAKSHMI

Kannuru, Krishna

Visakhapatnam, Andhra Pradesh

S.No. NP-APEPD26-11117547

Estimation for Supply of 3KW Solar Power Generating System (SPGS) - On-grid for Net meter

Solar Panel: 3000W SovaSolar/APS/Luminous make DCR Solar Panel Solar Inverter: 3kVa Grid Tie Solar Inverter (IEC/BIS Approved) Accessories: 4Sq. Copper AC Cable, 4Sq. Copper DC cable GI Mounting Structure (North Pole-8 Feet, South Pole-6 Feet) AC-DCDB, Earthing, 1" PVC Pipe, Flexible PVC Pipe GI/SS Nuts, Bolts & Hardware	Price (Including GST)	Rs.220,000.00
	Discount	Rs.20,000.00
	Final Amount	Rs.200,000.00
	Application Charge	Actuals
	Net Meters Cost	Actuals (Estimating given by APEPDCL)
	MNRE SRT National Solar Portal Subsidy	Rs.78,000.00
		(Rs.30,000 x 2kW = Rs.60,000/- Rs.18,000 x 1kW = Rs.18,000/-)

The above prices are for the complete SPV kit which includes SPV modules, Solar Inverter, Structure & all Accessories. Fabricated Shed, High Rise Structure, Civil Work, Net Meter Equipment, Extra cables (AC-DC), Contract Load Enhancement Charges, Special Drawings & Internal Wiring are customer scope.

Above system designed for S.No. NP-APEPD26-11117547

Discom Sanction Load: 3KW-Cat-1-Phase-1

Terms and Conditions:

1. Taxes: GST Included 2. Payment terms: 100% Advance upon placing order. 3. Delivery: 2-4 weeks

Our Banking Details (CC Account)

A/c Name: Visionera Pvt Ltd

A/c No.: 50200078831450

Bank: HDFC, NAD Kotharoad

NEFT/RTGS/IFSC: HDFC0001604

Product Warranty

Modules: As per MNRE guidelines IEC/BIS standards

- 10-year workmanship warranty (Minimum power output 90% for first 10 years; 80% from Year 11 to 25)
- 25 Years Life

Solar Inverter: As per IEC/BIS Standard

- 5 year warranty against manufacturing defects

Authorised Partners

